

DAVID D. BROWN  
CHAIRMAN

DAVID F. BRANDT  
VICE-CHAIRMAN

CLARENCE O'CONNOR  
COMMISSIONER

KENNETH PAQUET  
COMMISSIONER

HENRY GINOP  
COMMISSIONER

## **Cheboygan County Road Commission**

5302 South Straits Highway  
Indian River, Michigan 49749

Phone: (231) 238-7775

Fax: (231) 238-0830

877-257-2272

R. BRENT SHANK  
ENGINEER/MANAGING DIRECTOR

DANA S. STEMPKY  
CLERK

### 2017 Stream Crossing Culverts

The Cheboygan County Road Commission will accept sealed bids for supplies pertaining to Culvert Materials. All Materials shall meet current *MDOT Standard Specifications for Construction, 2012*.

The Culverts shall be made of galvanized steel unless otherwise specified. Lengths and Sizes specified on Bid Sheet.

Bids shall be submitted on the enclosed CCRC Bid Sheet (attached) in a sealed envelope clearly indentifying the bidder and marked "Culvert Materials".

Bidders shall include written statement of allowable discounts and terms of payment. Bid prices shall be valid for a period of one year from date of award.

Prices Shall include delivery to CCRC project.

Bids are due at **2:00 p.m. on Tuesday, May 30, 2017**, at which time, the bid will be publicly opened and read aloud.

Cheboygan County Road Commission reserves the right to accept or reject any and all bids, in whole or in part; to waive irregularities or informalities; and to award bids, in whole or in part, as deemed to be in the best interest of the Cheboygan County Road Commission.

Travis Horrocks, P.S.  
Engineer Technician  
[engtech@chcrc.com](mailto:engtech@chcrc.com)  
(231)238-7775

Enclosures

**Cheboygan County Road Commission**  
**2017 Stream Crossing Culverts**

(To be completed by bidder in ink or typewritten)

Company Name: \_\_\_\_\_

Address: \_\_\_\_\_

City: \_\_\_\_\_ State: \_\_\_\_\_ Zip: \_\_\_\_\_

Phone: \_\_\_\_\_ Fax: \_\_\_\_\_

Contact Person w/Title: \_\_\_\_\_

E-Mail: \_\_\_\_\_

**Indian Trail Road at Mullett Creek, Section 35, T37N, R3W, Munro Township**

- Main Channel: Culv, CSP Arch, Cl A, 112 inch by 75 inch. Length: 65 feet, Ends Mitered 1:2 Lifting Lugs Installed.

\$ \_\_\_\_\_ Lead Time: \_\_\_\_\_

- Tributary: Culv, CSP Arch, Cl A, 95 inch by 67 inch. Length: 83 feet, Ends Mitered 1:2. Lifting Lugs Installed

\$ \_\_\_\_\_ Lead Time: \_\_\_\_\_

- Ditch Culvert: Culv, Cl E, 48 inch. Length 55 feet.

\$ \_\_\_\_\_ Lead Time: \_\_\_\_\_

**Crump Road at Mullett Creek, Section 35 & 36, T37N, R3W, Munro Township**

- Main Channel: Culv, CSP Arch, Cl A, 142 inch by 91 inch. Length: 63 feet, Ends Mitered 1:2. Lifting Lugs Installed.

\$ \_\_\_\_\_ Lead Time: \_\_\_\_\_

**Budzinski Road at Mullett Creek, Section 1, T36N, R3W, Burt Township**

- Main Channel: Culv, CSP Arch, Cl A, 142 inch by 91 inch. Length: 66 feet, Ends Mitered 1:2. Lifting Lugs Installed.

\$ \_\_\_\_\_ Lead Time: \_\_\_\_\_

**SUPPLIER NAME:** \_\_\_\_\_

**Cope Road at Sturgis Creek, Section 14, T34N, R1E, Forest Township**

- Main Channel: Culv, CSP Arch, Cl A, 142 inch by 91 inch. Length: 74 feet, Ends Mitered 1:2. Lifting Lugs Installed.

\$ \_\_\_\_\_ Lead Time: \_\_\_\_\_

**Hatch Road at Little Sturgeon River, Section 5, T34N, R2W, Ellis Township**

- Main Channel: 18 foot 7 inch by 5 foot 4 inch by 40 feet long Aluminum Plate Box Culvert (Bottomless). Ends Square. Footer plates, Blue Prints and Hardware included. Cover is approximately 2.9 feet.

Specify Thickness: \_\_\_\_\_ Specify Manufacture: \_\_\_\_\_

\$ \_\_\_\_\_ Lead Time: \_\_\_\_\_

All prices shall be F.O.B. Cheboygan County Road Commission Project Locations

Cheboygan County Road Commission reserves the right to accept or reject any and all bids, in whole or in part; to waive irregularities or informalities; and to award bids, in whole or in part, as deemed to be in the best interest of the Cheboygan County Road Commission.

Allowable Discounts and/or Payment Terms

---

---

---

**Note: All materials must meet current MDOT Stand Specifications for Construction, 2012.**

\_\_\_\_\_  
Authorized Signature

\_\_\_\_\_  
Date

\_\_\_\_\_  
Printed Name