

DAVID D. BROWN
CHAIRMAN

DAVID F. BRANDT
VICE-CHAIRMAN

RICHARD A. LAHAIE
COMMISSIONER

KENNETH PAQUET
COMMISSIONER

HENRY GINOP
COMMISSIONER

Cheboygan County Road Commission

5302 South Straits Highway
Indian River, Michigan 49749

Phone: (231) 238-7775

Fax: (231) 238-0830

877-257-2272

R. BRENT SHANK
ENGINEER/MANAGER

DANA S. STEMPKY
CLERK

June 5, 2019

BID ADDENDUM NO. 1

Project: **2019 Inverness Township Paving Project**

A489.501 - Wing Road, Laperall Road to Riggsville

A489.502 - Wing Road, M-27 to Indian Trail Road

A489.503 – Indian Trail Road, Wing Road to M-27

The quantity for Protective Ovly, Snowmobile Trail Crossing (44 Syd) was not in original bid sheet.

Attached is a corrected Bid Sheet.

The HMA Application Table was in error for Indian Trail Road. Below is the corrected Table.

HMA APPLICATION TABLE					
Label	Mix	Application Rate (Lbs/Syd)	Design Performance Grade	Comments	Pay Item
T	HMA,4E1	220	58-28	Main Line	HMA, 4E1
A	HMA,4E1	220	58-28	Approach	HMA Approach
1	AWI = 220 for all HMA, 4E1				
2	Apply HMA Bond Coat at 0.10 gallons per square yard between paving courses or as directed by the Engineer. Paid for as part of other HMA items.				

CHEBOYGAN COUNTY ROAD COMMISSION

Travis L. Horrocks, P.S.
Engineer Technician

Board of Cheboygan County Road Commissioners
5302 South Straits Highway
Indian River, MI 49749

Bid Sheet

Board of Cheboygan County Road Commissioners
 5302 South Straits Highway
 Indian River, MI 49749

To whom it may concern:

The undersigned proposes to furnish any and all materials, labor, and equipment necessary for the reconstruction of Canton Road & W. Black Lane as spelled out in the "Invitation to Bid" for the prices below.

The Cheboygan County Road Commission reserves the right to reject any and/or all bids based on what is in the best interest of Cheboygan County.

Project:

A489.501 Wing Road Road (Laperall Road to Riggsville Road)

Item	Quantity	Unit	Unit Price	Total
Mobilization	1	LSUM		
Shoulder, CI II	400	Ton		
HMA, 4E1	1700	Ton		
Pavt Mrkg, Waterborne, 4 inch Yellow	11500	Ft		
Traffic Control	1	LSUM		
A489.501 TOTAL COST ESTIMATE =				

Project:

A489.502 Wing Road (M-27 to Indian Trail Road)

Item	Quantity	Unit	Unit Price	Total
Mobilization	1	LSUM		
Aggregate Base	525	Ton		
HMA Base Crushing & Shaping	3494	Cyd		
Approach, CI I	70	Ton		

Bid Addendum No. 1, Corrected Bid Sheet, June 5, 2019

Shoulder, Cl II	65	Ton		
Trenching	24	Sta		
HMA Surface, Rem	614	Syd		
HMA, 4E1	350	Ton		
HMA Approach	43	Ton		
Pavt Mrkg, Waterborne, 4 inch Yellow	560	Ft		
Traffic Control	1	LSUM		
Restoration	750	Syd		
Monument, Box	1	Ea		
A489.502 TOTAL COST ESTIMATE =				

Project:

A489.503 Indian Trail Road (Wing Road to M-27)

Item	Quantity	Unit	Unit Price	Total
Mobilization	1	LSUM		
Stump, Rem, 6 inch to 18 inch	6	Ea		
Culv, Rem, Less than 24 Inch	3	Ea		
Ditch Cleanout	8	Sta		
Aggregate Base	700	Ton		
Geotextile, Stabilization	4470	Syd		
High Performance Biaxial Geogrid	4470	Syd		
HMA Base Crushing & Shaping, MOD	4470	Syd		
Approach, Cl I	25	Ton		
Shoulder, Cl II	150	Ton		
Culv, Cl A, 12 inch	60	Ft		
Culv, Cl A, 15 inch	50	Ft		
HMA, 4E1	440	Ton		

Bid Addendum No. 1, Corrected Bid Sheet, June 5, 2019

HMA Approach	35	Ton		
HMA Surface, Rem	128	Syd		
Post, Mailbox	6	Ea		
Pavt Mrkg, Waterborne, 4 inch Yellow	2000	Ft		
Protective Ovly, Snowmobile Trail Crossing	44	Syd		
Traffic Control	1	LSUM		
Riprap. Plain	3	Syd		
Restoration	900	Syd		
A489.503 TOTAL COST ESTIMATE =				

TOTAL COMBINED COST ESTIMATE =	
--------------------------------	--

Bidder: _____

Address: _____

Signature: _____

Phone No.: _____

Printed Name: _____

Date: _____

Title: _____

Email: _____